RESOLUTION NO. R-15-89

A RESOLUTION TO AUTHORIZE THE ISSUANCE OF A PURCHASE ORDER TO SAFE SLIDE RESTORATION FOR THE REPAIR AND REPAINTING OF TWO WATERSLIDES AT THE COFFEYVILLE AQUATIC CENTER.

BE IT RESOLVED by the Board of Commissioners of the City of Coffeyville, Kansas that the Finance Director be and is hereby authorized and directed to issue a purchase order in the amount of $58,800 to Safe Slide Restoration for the repair and repainting of two waterslides at the Coffeyville Aquatic Center.

ADOPTED THIS 12th DAY OF JULY, 2016.

_____
Craig C. Powell, Mayor

ATTEST:

_____
Cindy Price, City Clerk

APPROVED AS TO FORM AND LEGALITY:

_____
Paul Kritz, City Attorney

Dale Cooper LLC DBA Safe Slide Restoration
P.O. Box 186, Fredericktown, MO 63645
314.448.7233 or 855.639.7543
www.safeslides.com

June 30, 2016

Coffeyville Aquatic Center/ Attn: Randy Barg
1906 N. Buckeye Street / Coffeyville, Kansas 67337
620.252.6139 / rbarg@coffeyville.com

Hello Randy,
Following is a proposal for the restoration of your slides. This proposal is based on the inspection our Project Manager did while visiting your facility. We are the only slide restoration company certified in fiberglass composites by the American Composite Manufactures Association (ACMA). We have **15-years** of experience working with fiberglass and gel coat.

- There is a **2 – year warranty** on the gel coat.
- There is a **5 - year warranty** on the structural fiberglass repair not to delaminate.
- There is a **5 - year warranty** on the paint for adhesion.

Slide Description:
Open Flume Body Slide – Blue
Closed to Open Flume Body Slide - Blue

Work Description:
Gel Coat - Interior:
- Repair all minor structural repairs in ride path* (minor repair does not require laminating)
- All repairs will be done with vinyl-ester resin
- Recaulk all seams (recaulking is not a guarantee to stop leaking seams)
- Seams will be caulked with a Sikaflex or 3M 4000
- Prepare interior ride path for Gel Coat
- Lay non-skid at start tub
- Refinish interior ride path of slide with Gel Coat
- Gel Coat will be applied to a thickness of 18 - 24 mils.
- Premium Gel Coat will be used

Paint - Exterior:
- Wash exterior of slide with cleaner
- Prime-coat bare areas as needed
- Paint exterior with Poly - Siloxane Paint

Project Amount for Paint ..... $ 12,000.00
Project Amount for Gel coat ..... $ 46,800.00
Total Project Amount .....$ 58,800.00

***Structural repair is defined as any damage that is an obvious threat to the guests, (i.e. a chip or scrape with a sharp edge). This is not to be confused with cosmetic repair, (i.e. a spider crack with no flaking or raised edge).**

If there are any chip repairs and gel coat is required; we are certified in field color-matching for gel coat. This is not to be confused with manufacturer's exact color matching. If there are any previous interior or exterior coatings; Safe Slide Restoration does not warranty any substrates previously coated after the manufacture's original coating, or any previous repairs. There will be an additional charge for failed coatings. Indications of failed coatings will warrant a second inspection for unstable previous repairs. Recaulking seams does not apply if the seams are fiberglassed over. If we are repairing leaking seams the customer is responsible for identifying the leaking seams. The cost of a lift is not included in the above pricing. If a lift is needed, we are not responsible for any broken concrete. Sometimes slides require a second coat of paint to achieve the desired finish. If a second coat of paint is required there will be an additional charge of 50 % of the original paint price. The pricing does not include the cost of state taxes or licenses, if required.

Safe Slide Restoration reserves the right to have adequate access to the project area to complete the project as efficiently as Safe Slide Restoration deems possible. This may require, but not limited too: working 12 hours a day / seven days a week. The park is responsible to provide an adequate water source and electric power for the duration of the job.

50% is due at commencement of project
50% is due at completion of project

After 30 days, an additional 5% will be added to the unpaid amount, and every 30 days thereafter that the payment is late. The park is responsible for any legal fees necessary to collect payment.

Signatures:

Coffeyville Aquatic Center: _____ Date: _____

Safe Slide Restoration: _____ Date: _____

(BL)OPENTGSF1536TPSF1689BG16P4SM
(BL)CLOSEDTGSF1170TPSF1287BG19P4SM